


QUOTATION

Sub: Providing of electrical installation in DOAA Canteen & newly Alloted Lab Space in C' PEB old-SAC.

S.N.	Description	Qty.	Unit	Rate (In Words & Figures)	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	3 X 1.5 Sq.mm	17.00	Mtr		
b	3 x 4 Sq.mm	37.00	Mtr		
c	3 X 10 Sq.mm	122.00	Mtr		
d	3 X 16 Sq.mm	15.00	Mtr		
2	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.	15.00	Mtr.		
3	Supplying and fixing following rating, 240 volts, 'C' series, minature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc as reqd.				
a	Single Pole (5 Amp to 32 Amp)	12.00	Nos.		
b	Tripple Pole (5 Amp to 32 Amp)	8.00	Nos.		
c	Four Pole (5 Amp to 32 Amp)	8.00	Nos.		
d	Four Pole (40 Amp to 63 Amp)	1.00	Nos.		
4	S & F metal enclosure suitable for DP/FP MCB/ on surface or recessed etc as reqd.	8.00	Nos.		

S.N.	Description	Qty.	Unit	Rate (In Words & Figures)	Amount
5	Supplying and fixing following modular switch/socket on the existing modular plate & switch box/ DLP plastic trunking including connections but excluding modular plate etc as reqd.				
a	5/6 amps switch	2.00	Nos.		
b	15/16 amps switch	40.00	Nos.		
c	3 pin 5/6 amps socket outlet	2.00	Nos.		
d	6 pin 15/16 amps socket outlet	40.00	Nos.		
e	Blanking Plate	2.00	Nos.		
6	Supplying and fixing following Modular GI/plastic base & cover plate on existing modular metal boxes/DLP plastic trunking etc. as required.				
a	1 or 2 Module	6.00	Nos.		
b	6 Module	20.00	Nos.		
7	Supplying and fixing following Module Plastic box for fixing modular switches/sockets in surface/recess etc as required.				
a	1 or 2 Module	6.00	Nos.		
8	Supply fixing connecting & commissioning of 5 Amp. 3 pin Plug top as reqd.	2.00	Nos.		
9	Fixing, Internet Box of size 75mm x 75mm x 40 mm including brass screw on surface / recessed as reqd.	16.00	Nos.		

S.N.	Description	Qty.	Unit	Rate (In Words & Figures)	Amount
10	Drawing of computer network cable/ PVC insulated flexible cooper/ Aluminium single core cable of size 1.5sqmm to 25 sqmm/ telephone cable upto 10 pair in existing pipe / casing and capping as reqd including numbering the wires at both the ends.	159.00	Mtr.		
11	Supply,Installation of exhaust fan 220 volt, 50 Hz of following sizes in the existing opening l/c connection, testing, commissioning etc as reqd.				
a	450 mm	2.00	Nos.		
12	S/F, Exhaust fan shutter of following sizes on rag bolts as reqd.				
a	450 mm	2.00	Nos.		
Total Rs.					


राघवेंद्र सिंह
RAGHVENDRA SINGH
 अधिकायी अभियंता (वि०) E.E. (Elect.)
 स० वि० वि०, भा० वि०, कानपुर
 I.W.D., I.L.T., Kanpur