


Quotation

Name of work : Providing additional 5Amp plug point in primary class rooms and library as requested by the principle Kendriya Vidyalaya.

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	3 x 1.5 Sq.mm..	100.00	mtrs		
b)	3 x 4 Sq.mm..	300.00	mtrs		
2	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a)	5/6 Amp switch	60.00	Nos.		
b)	15/16 Amp. switch	2.00	Nos.		
c)	3 Pin 5/6 Amp. socket outlet	60.00	Nos.		
d)	6 Pin 15/16 Amp. socket outlet.	2.00	Nos.		
3	Providing and fixing casing and capping in place of defective and damaged wood batten including dismantling of betten and wire & relaying of wires as required complet.				
a)	20 x 12 mm	100.00	Mtr.		
b)	25 x 16 mm	100.00	Mtr.		
4	S & F wooden board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
a)	100 mm x 100 mm	15.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
b)	175 mm x 100 mm	10.00	Nos.		
c)	200 mm x 150 mm	10.00	Nos.		
d)	200 mm x 250 mm	2.00	Nos.		
e)	250 mm x 300 mm	2.00	Nos.		

Total Rs.


 राघवेंद्र सिंह
 RAGHVENDRA SINGH !
 अभियांत्रिकी अध्यापक (दि०) E.E. (Elect.)
 सं० नि० वि०, का० प्रौ० संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur