

INSTITUTE WORKS DEPARTMENT  
ELECTRICAL DIVISION

No. ED/EE/408

Dated: 25-11-2020

**QUOTATION NOTICE**

M/s .....  
.....  
.....  
.....

Dear Sirs,

Sealed quotations are invited from the authorized dealers/ specialized agency by the undersigned on behalf of the Director, IIT Kanpur, " **Repairing & Maintenance of Solar water heating system installed at A, B, C Blocks of Hall-12 and other associated work in order to make it operational.**" As per enclosed Bill of Quantity/ overleaf, so as to reach in this office on or before 02-12-2020 up to 3.00 PM and the quotation will be opened on the same day at 3.30PM in the presence of quotationers or their representative who want to be present.

**The terms and conditions of the quotation are as under:**

1. The quotations should be submitted in a properly sealed envelop, addressed to the undersigned. The enquiry nos. and date should invariably quoted on the top of the envelop.
2. The time allowed for carrying out the above noted work is 28(Twenty Eight) Days.
3. The rates quoted should be exclusive of GST, no other tax is payable except GST. GST shall be quoted separately.
4. Security @ 7.50% shall be deducted from the bills which shall be released on successful completion of defect liability period of six months.
5. Earnest Money of **Rs.2,120/-** is to be submitted in the form of FDR pledged in favour of the Director, IIT Kanpur alongwith the quotation. The earnest money of the unsuccessful quotationers will be returned within one month's time. (Estimated cost **Rs.1,05,993.00**)
6. The quotations shall remain valid for 90 days from the date of opening.
7. Income tax & Trade tax will be recovered as per Government norms from the bill and the amount so recovered will be deposited in the State Bank of India at the credit of the firm.
8. The earnest money/Security deposit will be regulated as per the norms of C.P.W.D.
9. The Institute reserves the right of accepting or rejecting any quotations without assigning any reason thereof.
10. The material should be used as per enclosed approved list of make.

## QUOTATION

**Name of Work:-** Repairing & Maintenance of Solar water heating system installed at A, B, C Blocks of Hall-12 and other associated work in order to make it operational.


S.	Description of Items	Qty	Unit	Rate (in words & Figures)	Amount
1	Dismantling, cleaning, descaling, overhauling of collectors & hot water pipe line of installed solar water heating system with proper chemical / liquid soap etc. and neutralizing the same complete as required.	60.00	Nos.		
2	Painting two coat of solar hot water complete system including collector stand, hot water storage and makeup tank stands, pipe sports after cleaning the surface with sand paper / cloth etc as reqd..	60.00	Nos.		
3	Dismantling and refixing solar Panel after repairing leakage in Solar panel pipe and removing air lock, cleaning choked line etc as required complete.	1.00	Nos.		
4	Supply fixing connecting & commissioning of 2/3 kW heating element in Solar water tank / geyser. as required complete	4.00	Nos.		
5	Supply fixing connecting & commissioning of thermostat suitable for geyser. as required complete	4.00	Nos.		
6	Supply fixing connecting & commissioning of 15/16Amp. rating 3 pin Plug top Anchor makeas reqd complete.	4.00	Nos.		
7	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.				
7.1	25 mm dia nominal bore	12.00	Mtr.		
8	Providing and fixing solar glass for flat plate collector of capacity 100 LPD complete as required.	1.00	Nos.		

S.	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
----	----------------------	-----	------	------------------------------	--------

7 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.

30.00 Kg.

Total Rs.

  
 RAGHVE . SINGH  
 अधिरापी अभियंता  
 सं० नि० वि०, सं० वि०  
 I.W.D., I.I.T., Kanpur  
 स्थान, कानपुर