


QUOTATION

Sub **Repairing and replacement of defective items in Director office and different labs and offices in academic area on complaints basis.**

S. No.	DESCRIPTION	Qty.	UNIT	RATE (In works & Figures)	AMOUNT
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 1.5 sq. mm	2.00	Metre		
2	Providing and fixing casing and capping in place of defective and damaged wood batten including dismantling & relaying of wire as required complete.				
a	20 mm x 12 mm	6.00	Meter		
3	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	5.00	No.		
b	3 pin 5/6 A socket outlet	4.00	No.		
4	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.				
a	20 watt ESENTIAL PHILIPS or equivalent Tube in place of 36/40 W FL tube	14.00	Nos.		
b	18 watt. LED PLL lamp	10.00	Nos.		
5	Supply and fixing of following LED light fixture with Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
a	36 watt recess mounting LED light fixture 600 x 600 mm	2.00	Nos.		

S. No.	DESCRIPTION	Qty.	UNIT	RATE (In works & Figures)	AMOUNT
6	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	2.00	Nos.		
7	Alteration of internal wiring in existing fitting of any type for retrofitting of tube LED i/c dismantelling & refixing as reqd.	24.00	Nos.		
8	Supplying and laying of one no. 4 x 16.0 sqmm PVC insulated, XLPE steel armoured aluminium conductor power cable of grade 1.1 kV as required complete in following manners.				
a	in open duct	3.00	Meter		
b	On Surface	28.00	Meter		
9	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
a	Triple pole and neutral 5 A to 32 A	1.00	No.		
10	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	1.00	Nos.		
11	Dismantling and refixing of M.S./PVC box of up to 250 x 300 x100 on surface recessed as required. including painting with enamel paint as reqd	21.00	Nos.		
12	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				

S. No.	DESCRIPTION	Qty.	UNIT	RATE (In works & Figures)	AMOUNT
a	4 X 16 sq. mm (28mm)	2.00	No.		
13	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	1.00	Nos.		
14	Supplying and fixing following size/ modules, pop, up type flush-mounting box equipped with "push and side" locking system to avoid accidental opening by feet suitable for Arteur socket outlet modular switches in recess etc as required.				
a	3 modules	2.00	Nos.		
	Total Rs.				


 राघवेंद्र सिंह
 RAGHVENDRA SINGH
 अधिरापी अभियंता (Gen) E.E. (E&T)
 संविधिक
 I.W.E.

Deat