


QUOTATION

Name of work :- Providing & fixing Electrical Installation work in existing Animal compound near Gas godown at IIT Kanpur.

S.N	Description of item	Qty.	Unit	Rate (In words & Figures)	Amount
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.				
1.1	Group A	4.00	Point		
2	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required.				
2.1	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	9.70	Mtr.		
3	Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required.	4.00	Each		
4	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required.				
4.1	100 mm X 100 mm X 60 mm deep	4.00	Each		
5	Supplying, fixing, testing & commissioning and testing of the following luminaries light fixtures with Electronic driver, LED Lamp, reflector, diffuser, MS housing etc complete with all accessories as required.				
5.1	LED tube light fitting (1 X 18 / 20 Watt. LED) surface mounting luminaires	4.00	Each		

Total Rs.


RAGHVENDRA SINGH
अधिकाारी अभियंता (वि.) E.E. (Elect.)
संनिविदा, सार्वजनिक बांधकाम, कानपुर
I.W.D., I.I.T., Kanpur
