

QUOTATION

Sub : Providing ups connectio in Low Temperature Extention in SL Extention and Samtal center room-305.


SL No.	DESCRIPTION	QtY	UNIT	RATE (In words & Figures)	AMOUNT
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
a	Group C	4.00	Point		
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 1.5 sq. mm	20.00	Metre		
b	3 x 2.5 sq. mm	61.00	Metre		
c	3 x 6 sq. mm	10.00	Metre		
d	3 x 10 sq.mm.	56.00	Meter		
3	Supplying and drawing following pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	2 Pair	11.00	Metre		
4	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	28.00	Meter		
5	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required				

SL No.	DESCRIPTION	Qty	UNIT	RATE (In words & Figures)	AMOUNT
a	32 mm	12.00	Meter		
6	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partion etc. as required complete.	18.00	Meter		
7	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
a	85 mm flexible cover	18.00	Meter		
b	End cap	8.00	Nos.		
c	Internal angles- adjustable from 80°-100°	4.00	Nos.		
d	external angles- adjustable from 60°-120°	2.00	Nos.		
e	flat junction	1.00	Nos.		
f	flat angles	1.00	Nos.		
g	separation partitions	15.00	Meter		
h	Joints for 85mm width cover	8.00	Nos.		
i	base joints	20.00	Nos.		
8	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	lor 2 Module	3.00	No.		
b	3 Module	6.00	No.		
c	6 Module	9.00	No.		
9	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
a	5/6 amps switch	5.00	No.		

SL No.	DESCRIPTION	Qty	UNIT	RATE (In words & Figures)	AMOUNT
10	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	25.00	No.		
b	15/16 A switch	7.00	No.		
c	3 pin 5/6 A socket outlet	21.00	No.		
d	6 pin 15/16 A socket outlet	7.00	No.		
e	Telephone socket outlet	1.00	No.		
11	Supplying and fixing following rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
a	Double Pole (40A-63A)	1.00	Nos.		
b	Triple pole (40A-63A)	1.00	Nos.		
c	Four Pole (40A-63A)	1.00	Nos.		
12	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a	3 Module	1.00	Nos.		
13	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	2.00	Nos.		
14	Supply and fixing of following LED light fixture with Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
a	18 watt surface mounting 300 x 300 mm LED light fixture	4.00	Nos.		

SL No.	DESCRIPTION	Qty	UNIT	RATE (In words & Figures)	AMOUNT
15	Supplying and fixing 32 amps, 230 volts, 2P+E industrial type, socket outlet, with 3 pin metal enclosed plug top along with 32 amps ' C ' series double pole MCB, in the sheet steel enclosure, on surface or in recess, with chained metal cover for the socket as required complete.	1.00	Nos.		
16	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	700.00	Meter		
17	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. ( box and cover plate will be supplied by dept.)	18.00	Nos.		

Total Rs.

  
 RAGHVENDRA SINGH  
 अधिरापी अधिकारी (वि०) E.E. (Elect.)  
 संविधि, मन्त्री कार्यालय, कानपुर  
 I.W.D., L.I.E., Kanpur  
