## QUOTATION

Name of Work:- Replacement of defective and damaged Gate Valve & nipples in Solar water heating system installed for Blocks of Hall-12 and other associated works

S. 1	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
1	Supplying and fixing testing and commissioning of fallowing Size valve IS marked size as mentioned below with insulation as per standard specification.	I			
a)	GM gate Valve 25 mm	8.00	Nos.		
b)	GM gate Valve 32 mm.	6.00	Nos.		
2	Providing and fixing of following size fo SS fittings in pipe line with complete as required				
a)	SS nipple Size of 1" x 6"	7.00	Nos.		
b)	SS nipple Size of 11/4" x 6"	28.00	Nos.		
c)	SS Union 32 mm	14.00	Nos.		
3	Providing & fixing 50 mm thick more than 48 Kg/cu Mtr glass wool insulation wrapped with wire mesh etc as required complete on 20/25/32 size hot water pipe line.	50.00	Mtrs.		
4	Providing & fixing 26 swg thick aluminium sheet cladding with screw make Hindalco or its equivalent approved make etc as required complete.	50.00	mtr.		
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	300.00	Kg.		
	Dismentalling & refixing of pipe line by providing & fixing required fittings etc complete	80.00	Mtrs.		
	Total Rs.				

राध्यक्त विह RAGHVENDRASINGH अधिकाची अभियंता (विक) E.E. (Elect.) संक्षिकविक, साक्ष्मीक संस्थान, कानपुर I.W.D., I.I.T., Kanpur