


QUOTATION

Name of Work:- Repairing & Maintenance of Solar water heating system installed at RA Tower.

S. No	Description of Items	Qty	Unit	Rate	Amount
				(in words & Figures)	
1	Providing & fixing 50 mm thick more than 48 Kg/cu Mtr glass wool insulation wrapped with wire mesh etc as required complete on following size hot water pipe line.	40.00	Sq Mtr.		
2	Providing & fixing 26 swg thick aluminium cladding bend with screw make Hindalco or its equivalent approved make etc as required complete.	40.00	Mtr.		
3	Supplying, fixing, testing & commissioning of CPVC coupler 15 mm make Prince or its equivalent make with solvent cement etc as reqd.	130.00	Nos.		
4	Supply fixing connecting & commissioning of MS clamp. as required complete	80.00	Nos.		
5	Providing and fixing solar glass for flat plate collector of capacity 100 LPD complete as required.	2.00	Nos.		
6	Supplying & fixing of CPVC brass elbow 15 mm etc as reqd.	80.00	Nos.		
Total Rs.					_____


13/04/21
PAUL BIRLA & SONS
Ward No. 1, Sector 10, Gurgaon
Haryana, India
LWD, Haryana
