

QUOTATION

Name of work: Electrical Maintenance work at south side residence as per enclosed complaints.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	1 x 1.5 Sq.mm.	3.00	Mtr.		
2	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a)	5/6 Amp switch	11.00	Nos.		
c)	15/16 Amp. switch	6.00	Nos.		
d)	3 Pin 5/6 Amp. socket outlet	5.00	Nos.		
e)	6 Pin 15/16 Amp. socket outlet.	5.00	Nos.		
3	supplying anf fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc as reqd.	1.00	Nos.		
4	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	1.00	Nos.		
5	Supplying and fixing brass batten/ angle holder including connection etc. as required.	4.00	Nos.		
6	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
a	4 module	1.00	Nos.		
b)	6 module	2.00	Nos.		
7	Supply & fixing modular blanking plate on existng metal boxes but excluding modular plate as req.	8.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
8	S/F following modular base & cover plate on existing modular metal boxes etc. as reqd.				
a)	3 module	3.00	Nos.		
b)	4 module	4.00	Nos.		
9	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	2.00	Nos.		
10	Dismantling and refixing of wood board of any size on surface or in recessed etc as reqd.	2.00	Nos.		
11	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator l/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a)	1200 mm	1.00	Nos.		
b)	1400 mm	1.00	Nos.		
12	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	7.00	Nos.		
13	S & F following piano type switch /socket on existing switch box/cover l/c connection etc as reqd.				
a)	Fan regulator socket type rotary/dimmer	3.00	Nos.		
14	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	340.00	Nos.		
15	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and with lamp as required complete.				
a)	LED tube light fitting (1 X 18 / 20 Watt. LED) surface mounting luminaires wipro meke	4.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
16	Supply, Installation of exhaust fan, 900 rpm 220 volt AC, 50 Hz of following sweep in the existing opening l/c connection, testing, commissioning etc as reqd.				
a	300 mm	1.00	Nos.		
17	Dismantling and refixing of switch / socket /regulator l/c cleaning, connecting, commissioning etc as reqd.	8.00	Nos.		
Total Rs					


 राघवेंद्र सिंह
 Raghendra Singh
 अभियांत्रिकी अभियन्ता (विद्युत) / E.E. (Elect.)
 स० नि० वि०, मा० प्र० संस्थान, काठपुर
 T.W.D., I.I.T. Kanpur
