


QUOTATION

Name of work :- Rewinding and overhauling of ceiling fans installed at House No. 4065, 169, 4084, 344, 195, 183 etc and other north side residences.

S.No.	Description of work	Qty.	Unit	Rate (In words & Figures)	Amount
1	Rewinding of following fans of following sizes i/c dismantling of rotor cutting the damaged winding and providing rewinding along with insulation paper, varnish, connecting copper leads of suitable quality including dismantling and refixing from normal/abnormal height and refixing as required. (Old burnt wire shall be reatin by the contractor.)				
a)	old model 48" / new model 56"	1.00	NOS		
2	Overhauling of fan of any size including dismantling and refixing of fan, bearings, checking, cleaning the all parts and supplying & replacement of rubber real, rubber rings, nut bolts, hanger clamps, bearing plates, cotter/ split pin, varnishing if reqd etc, reassembling testing and commissioning of fan as required complete.	56.00	Nos.		
3	Supplying and fixing 2.5 mfd capacitor suitable for ceiling fan.	24.00	Nos.		
4	Repairing of housing of bearing side /bush side /in fan body in ceiling fan /exhaust fan/ rally fan etc.	9.00	Nos.		
5	Cartage of Ceiling fans and regulator / exhaust fan From store to site as reqd.	16.00	Nos.		
6	Supply of following size ball bearings.				
a)	Ball bearing 6201 (NBC - make)	11.00	Nos.		
b)	Ball bearing 6202 (NBC - make)	13.00	Nos.		
Total Rs.					


अधिकायी अधियन्ता (विद्युत्)/E.E. (Elect.)
संलग्निविधि, माठ प्रीठ संस्थान, कानपुर
I.W.D., I.I.T. Kanpur

