


## QUOTATION

Name of work:-Replacement of old & damaged starter for 3-phase motor of fire system installed at the roof top of AA-Block New SBRA.

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	3 x 6 Sq.mm..	5.00	Mtr.		
2	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	1.00	Nos.		
3	Dismantling damaged DB/TPN Switches/ loose wire boxes along with all accessories and depositing the same in the store as reqd.	2.00	Nos.		
4	Supplying & fixing Connecting , testing & commising,Heavy duty automatic star delta starter Type DX-P suitable for 7.5 HP 3 phas indution motor 415V, 50Hz make C & S.(Cat No.BE3-DXP204-312)	1.00	Nos.		

**Total Rs.**

  
RAGHUBHUSHI SINGH  
अधिराशी अधीन (Elect)  
संनिधि, कानपुर  
I.W.D., I.I.I., Kanpur  
