

QUOTATION

Sub:- Replacement of damaged and faulty power cable of Lab-103 and lift at NCL from switch room.

| SL No. | DESCRIPTION | QTY | UNIT | RATE (in words & Figures) | AMOUNT |
|--------|---|--------|-------|------------------------------|--------|
| 1 | Supplying and laying of one no. 3.5 x 50.0 sqmm PVC insulated, XLPE steel armoured aluminium conductor power cable of grade 1.1 kV as required complete in following manners. | | | | |
| a | in ground I/c excavation, sand caushioning, protective covering and refixing the trench etc as reqd | 35.00 | Meter | | |
| b | In Pipe | 2.00 | Meter | | |
| c | in open duct | 8.00 | Meter | | |
| d | On Surface | 5.00 | Meter | | |
| 2 | Supplying and laying of one no. 4 x 16.0 sqmm PVC insulated, XLPE steel armoured aluminium conductor power cable of grade 1.1 kV as required complete in following manners. | | | | |
| a | in open duct | 10.00 | Meter | | |
| b | On Surface | 110.00 | Meter | | |
| 3 | Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd. | 5.00 | Nos. | | |
| 4 | Digging trench for taking out cable upto 400 Sq.mm. and refilling , watering ,ramming the same after taking out cable as reqd complete. | 30.00 | Meter | | |

| SL No. | DESCRIPTION | QTY | UNIT | RATE | AMOUNT |
|--------|-------------|-----|------|------|--------|
|--------|-------------|-----|------|------|--------|


(in words & Figures)

5 Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.

a 3½ X 50 sq. mm (35mm) 2.00 No.

b 4 X 16 sq. mm (28mm) 2.00 No.

Total Rs.


अभिजापी अभियन्ता (वि०) / E.E. (Elect.)
सं०नि०वि०, मा० प्रौ० संस्थान, कानपुर
I.W.D., I.I.T. KANPUR
