

## QUOTATION

**Name of work:-Repairing/replacement of faulty cable,in primary section of kendriya vidyalaya in the campus.**

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Supplying and making indoor end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1kV grade as reqd.				
a)	2x25 sq.mm.	2.00	Nos.		
2	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep)and re-filling etc as required				
a)	80 mm	5.00	Mtr.		
3	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 kV grade as required.				
a)	2x25 sq.mm.	2.00	Nos.		
4	Digging cable trench, lifting brick & cable for locating fault and relaying the cable i/c refilling the trench, extra sand if required shall be i/c in the item of following size. as required.	10.00	Mtr.		
5	Locating fault in the cable lines with meager etc. and rectifying removing & restoring supply the same & making good the damages etc as reqd.	1.00	Nos.		

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					

6 Supplying & Laying of one no. XLPE sheathed aluminum conductor steel armoured power cable of size 2 x 25 sq.mm. 1.1kV grade in following manners.

- |    |  |       |      |  |  |
|----|--|-------|------|--|--|
| a) | direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd. | 30.00 | Mtr. |  |  |
| b) | In pipe  | 3.00  | Mtr. |  |  |
| d) | On surface with MS clamp   | 15.00 | Mtr. |  |  |

**Total Rs**

\_\_\_\_\_

\_\_\_\_\_

*(Handwritten signature)*

प्रमाणित किया जाता है कि उपरोक्त विवरण सही है।  
 I.W.D. का कार्य।  
*(Handwritten signature)*