


## QUOTATION

Name of work :- Testing , repairing / replacement of electric energy meter as per enclosed complaints.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a	3 x 1.5 Sq.mm..	5.00	Mtr.		
2	Dismantalling damaged Switch /DB/KWH meter/pole fuse / loose wire box of any size from site and depositing in store l/c cartage etc. as reqd.	5.00	Nos.		
3	Supplying, fixing, connecting, testing & commissioning single phase electronic kWH meter LCD type of following ratings i/c. sealing the same (sealing material will be supplied by the dept.) etc as reqd.				
a	10-60 A, 230V, 50 Hz	4.00	Nos.		
4	Repairing, servicing, testing and commissioning 1 or 3 phase kWH meter l/c sealing the same (sealing material will be supplied by the dept.)	5.00	Nos.		
5	Supplying, fixing, connecting, testing & commissioning direct operated or CT operated 100/5A three phase electronic kWH meter LCD type of following ratings i/c. sealing the same (sealing material will be supplied by the dept.) etc. as reqd.				
a	100/5A , 415V, 50 Hz	1.00	Nos.		

**Total Rs**

  
अविभागी अमेरिका (वि)/ए.ए. (Elect)  
सावित्री, भा. प्रौ. संस्थान, कन्नूर  
A. W. D., J. J. T. Kannur

