

QUOTATION

Name of work -: Repairing & Replacement of defective switch/ socket, casing & capping, distribution boards etc.
At house No. 360,RA S-404,D-401,D-507,S-111,Campus school,607,S-226,S-504,495,S-511,S-119,S-315, S-616,662, 3043,S-202,S-419,D-503,S-230,S-607,S-212,D-108, S-213,S404,D-203,384 etc north side drive residences as per enclose complaints at IIT Kanpur.

S.No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(In words & Figures)					
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required.				
1.1	Group B	1.00	Points		
2	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
2.1	3 x 1.5 Sq.mm..	21.00	Mtr.		
2.2	3 x 4 Sq.mm..	10.00	Mtr.		
3	Supplying and fixing following piano type switch /socket on existing switch box/cover l/c connection etc as reqd.				
3.1	5/6 Amp switch	13.00	Nos.		
3.2	15/16 Amp. switch	2.00	Nos.		
3.3	3 Pin 5/6 Amp. socket outlet	9.00	Nos.		
3.4	6 Pin 15/16 Amp. socket outlet.	1.00	Nos.		
4	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
4.1	5/6 Amp switch	9.00	Nos.		

S.No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
4.2	15/16 Amp. switch	2.00	Nos.		
4.3	3 Pin 5/6 Amp. socket outlet	3.00	Nos.		
4.4	6 Pin 15/16 Amp. socket outlet.	2.00	Nos.		
4.5	Fan regulator socket type rotary step	3.00	Nos.		
4.6	Blanking plate	1.00	Nos.		
5	Supplying and fixing following modular base & cover plate on existing modular metal boxes etc. as reqd.				
5.1	3 module	1.00	Nos.		
5.2	4 module	1.00	Nos.		
5.3	6 module	2.00	Nos.		
6	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd.	5.00	Nos.		
7	Supplying and fixing brass batten/ angle holder including connection etc. as required.	18.00	Nos.		
8	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
8.1	20 x 12 mm	27.00	Mtr.		
8.2	25 x 16 mm	13.00	Mtr.		
9	Supplying and fixing following piano type switch /socket on existing switch box/cover l/c connection etc as reqd.				
9.1	Fan regulator socket type rotary/dimmer	3.00	Nos.		

S.No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
10	Supply and fixing and connecting & commissioning following CFL / lamps in existing fitting as reqd.(Make- Phillips or equivalent)				
10.1	LED tube light 18 / 20 Watt.	3.00	Nos.		
11	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
11.1	1200 mm	8.00	Nos		
12	Supplying and fixing 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	5555.00	Sq.cm		
13	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	7.00	Nos.		
14	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	28.00	Nos.		
15	Dismantling and refixing of wooden board of any sizess on surface or in recessed etc as reqd.	12.00	Nos.		

Total Rs

[Handwritten Signature]

श्रीमती श्रीमती (मि) / ई ई (Elect.)
 नमो-१६, नमो, श्रीमती, कामपुर
 (In words & Figures)

[Handwritten Signature]