


QUOTATION

Name of work:-Replacement of defective/damaged current transformers installed in metering panels in Faculty Apartment in the campus as per enclosed complaint.

S.No.	Description	Qty.	Unit	Rate (in words & figures)	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a)	1 x 10 Sq.mm..	10.00	Mtr.		
2	Supplying, fixing, connecting and commissioning of following rating tap wound current transformers class 1, ISF < 5 for metering, <i>CT Ratio: 60/5</i> <i>VA = 5</i>	10.00	Each.		
3	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required.	1.00	Mtr.		
Total Rs.					_____


आंध्रप्रदेश अनियता (वि०) E.E. (Elect.
संनिविदा, मातृप्रौठ संस्थान, कानुपुर
I.W.D., I.I.T., Kanpur
Pradi