


QUOTATION

Name of work:- Repairing of HT cable going from 33KV Substation to Substation No. 7.

S..N	Description of item	Qty	Unit	Rate	Amount
(In words & Figures)					
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 11 KV grade of following size in the existing masonry open duct as required.				
a	Above 120 sq. mm and upto 400 sq. mm	5.00	Mtr		
2	Supplying and making straight through cable jointing with heat shrinkable jointing kit complete with all accessories including ferrules suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required :				
a	240 sq. mm	2.00	Each		
3	Locating fault in LT/HT cable lines with meggar etc and rectifying removing & restoring the same and making good the damages etc as required..	4.00	Nos.		

Total Rs.


अधिकारी अभियंता (विद्युत) E.E. (Elect.
सहायक, माध्यम वोल्टता, काठगुड
(W.D., I.L.T., Kumbhar
Deer