

QUOTATION

Name of work:-Providing ,fixing,connecting,testing and commissioning of exhaust fans in class rooms & activity rooms in Kendriya Vidyalaya in the campus.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	3 x 1.5 Sq.mm.	120.00	Mtr.		
2	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a)	5/6 Amp switch	7.00	Nos.		
3	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd.	7.00	Nos.		
4	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	110.00	Mtr.		
5	Supply, Installation of exhaust fan, 1400 rpm 220 volt AC, 50 Hz of following sweep in the existing opening I/c connection, testing, commissioning etc as reqd.				
a)	380 mm	7.00	Nos.		
6	S & F, Exhaust fan shutter for following sizes exhaust fan on rag bolts as reqd.				
a)	375 mm	7.00	Nos.		


S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
-------	-------------	------	------	------------------------------	--------

7	Dismantling of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	90.00	Nos.		
---	--	-------	------	--	--

8	Supplying and fixing wood board/plastic board of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front etc as required.				
---	--	--	--	--	--

a)	100 mm x 100 mm	10.00	Nos.		
----	-----------------	-------	------	--	--

Total Rs.


 अधिशापी अभियन्ता (वि०)/E.E. (Elect.)
 संरक्षित, आ० प्रौ० संस्थान, कानपुर
 I.W.D. I.I.T. Kanpur
