


QUOTATION

Name of work :-Replacement of damaged LAN wire in H. No. 146, 1068, 304 and 305 as per enclosed complaints at IIT Kanpur.

S.No	DESCRIPTION	Qty	UNIT	RATE (in words & Figures)	Amount
1	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep)and re-filling etc as required				
a)	50 mm	10.00	Mtr.		
2	Supply and laying of HDPE pipe ISI mark of 25 mm (8Kg / cm ²) size outer dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a)	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	135.00	Mtr.		
b)	In pipe	11.00	Mtr.		
c)	In open duct	3.00	Mtr.		
d)	On surface with MS clamp	5.00	Mtr.		
3	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	45.00	Mtr.		

S.No	DESCRIPTION	Qty	UNIT	RATE (in words & Figures)	Amount
4	Drawing of optical cable enhanced cat 5/cat 6/telephone/ networking /power cable in existing steel conduit pipe/GI /HDPE pipe including numbering of networking wire from room to rack as reqd.	340.00	Mtr.		
5	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.		
Total Rs.					_____


 अधिशाही इंजीनियर (Elect.)
 संविधिक, माध्यम विद्यालय, कानपुर
 I.W.D., I.I.T., Kanpur
