

QUOTATION

Name of work:- Repairing of damaged 11KV cable going from Substation no. 5 to Substation No. 8.

S.No.	Description of item	Qty	Unit	Rate (In words & Figures)	Amount
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 11 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.				
a	Upto 120 sq. mm	10.00	Meter		
2	Supplying and making straight through cable jointing with heat shrinkable jointing kit complete with all accessories including ferrules suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required :				
a	50-95sqmm	2.00	Each		

Total Rs.


अधिसारी अभियंता (वि.) E.E. (Elect.
संनिविदा, वा0प्रौ0 संस्थान, कानपुर
I.W.D., I.L.L., Kanpur

३