

## QUOTATION


Name of work:- Repairing /replacement of old and damaged power cable feeding power to Cyber Security building from Animal House AC plant and providing 4 run GI pipes for cables crossing New RCC road near Engineering Science Building 2 (ESB 2) with allied electrical works.

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 kV grade as required.				
a)	3½ X 300 sq. mm	1.00	Each		
2	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep)and re-filling etc as required				
a)	100 mm dia	48.00	Mtr.		
3	Providing, laying and fixing following dia G.I. pipe (medium class) end cap (100 mm) complete as required.				
a)	End Cap (100 mm)	8.00	Nos.		
4	Digging cable trench, lifting brick & cable for locating fault and relaying the cable i/c refilling the trench, extra sand if required shall be i/c in the item of following size. as required.				
a)	Above 185 sq.mm up to 400 sq mm	40.00	Mtr		

Total Rs.

\_\_\_\_\_

\_\_\_\_\_

  
अधिकाकी अमियता (याग) E.E. (A.C.)  
अनिअरिओ, माओओ सस्थान, कानपुर  
W.D 1.1.1 Kanpur