

QUOTATION

Sub:- Providing power points & internet point in Animal House, NL-I-ME office, Old SAC, High Speed and Exhaust fan with points in Helicopter building.

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 1.5 sq. mm	43.00	Metre		
b	3 x 2.5 sq. mm	42.00	Metre		
c	3 x 4 sq. mm	34.00	Metre		
2	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	100.00	Meter		
3	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
a	internal / external angle	11.00	Nos.		
b	changeable flat angle	15.00	Nos.		
c	flat junction	2.00	Nos.		
4	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partion etc. as required complete.	1.00	Meter		
5	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
a	End cap	2.00	Nos.		
6	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as				
a	6 module	7.00	Nos.		
7	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	33.00	No.		
b	15/16 A switch	15.00	No.		
c	3 pin 5/6 A socket outlet	29.00	No.		
d	6 pin 15/16 A socket outlet	15.00	No.		
e	Blanking Plate	3.00	No.		
8	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	1.00	No.		
9	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	lor 2 Module	3.00	No.		
b	3 Module	8.00	No.		

Sl No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
c	6 Module	12.00	No.		
10	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a	1 or 2 Module	3.00	Nos.		
b	3 Module	6.00	Nos.		
c	6 Module	11.00	Nos.		
11	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by	245.00	Meter		
12	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	7.00	Nos.		
13	Supply fixing connecting & commissioning of following rating ISI marked 3 pin Plug top Anchor make as reqd complete.				
a	5 Amp	2.00	Nos.		
14	S & F following size of steel flexible pipe alongwith the accessories on surface etc as				
a	20 mm	10.00	Meter		


SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
15	Supply Installation, testing and commissioning of following ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable etc. as required.				
a	1200mm sweep.	1.00	Nos.		
16	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	2.00	Nos.		
17	Dismantling concealed & damaged DB/TPN Switches/starter/ loose wire boxes along with all accessories and depositing the same in the sectional store repairing the damages as reqd complete.	2.00	Nos.		
18	Fixing 20/25/32 mm conduit pipe/ DLP on surface with clamp/in recessed only conduit pipe supplied by department.(Free of cost)	10.00	Meter		
19	Supply, Installation testing and commissioning of following seep, copper wound, 900 RPM, 220 volt AC, 50 Hz exhaust fan in the existing opening etc as required				
a	450 mm / 18" sweep	2.00	Nos.		
20	Supplying and fixing exhaust fan shutter for following sizes exhaust fan on rag bolts as reqd complete.				
a	for 450 mm / 18" sweep	2.00	Nos.		

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
--------	-------------	-----	------	------	--------

(In words & Figures)

- | | | | | | |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------|--|--|
| 21 | Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required. | 2.00 | No. | | |
| 22 | Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required. | 2.00 | Metre | | |

Total Rs.


 अधिकारी ओरेशाना (वि.) / E.E. (Elect.)
 कर्मचारी, भाग पीठ सरधान कानपुर
 I.W.D., I.I.T. Kanpur
