


## QUOTATION

Name of work:- Providing internet point in each room and LAN wire for wi-fi access points in common area in new type 2 community centre.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. ( box and cover plate will be supplied by dept.)	18.00	Nos.		
2	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	525.00	Mtr.		
3	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	80.00	Mtr.		
b)	25 x 16 mm	50.00	Mtr.		
c)	32x 16 mm	50.00	Mtr.		
4	Supply and laying of HDPE pipe ISI mark of 40 mm (8Kg / cm <sup>2</sup> ) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.	200.00	Mtr.		
5	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required.				
a)	50mm dia	10.00	Mtr.		
6	S & F metal box of following sizes ( nominal size ) on surface or in recess with suitable size of phenolic laminated sheet cover in the front I/c painting etc as reqd.				
a)	200 mm x 150 mm x 60 mm deep	5.00	Nos.		

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
7	Laying of one no. PVC insulated, PVC sheathed / XLPE power cable of 1.1kV grade of size not exceeding 35 sq.mm.				
a)	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	55.00	Mtr.		
b)	In pipe	8.00	Mtr.		
c)	In open duct	10.00	Mtr.		
d)	On surface with MS clamp	15.00	Mtr.		

Total Rs.

  
 अधिशासी अभियंता (140) E.E. (Elect.  
 सॉफ्टवेयर, भाद्रपूर संस्थान, काठमांडू  
 I.W.D., I.I.T., Kanyu.