

QUOTATION

Sub:- Replacement and rerouting of submain wires from floor panel to DB of Lab No. 201 at new core labs.

SL No.	DESCRIPTION	Qty.	UNIT	RATE (In words & Figures)	AMOUNT
1.00	Supplying and laying of one no. 3.5 x 25.0 sqmm PVC insulated, XLPE steel armoured aluminium conductor power cable of grade 1.1 kV as required complete in following manners.				
1.01	in open duct	120.00	Meter		
1.02	On Surface	10.00	Meter		
2.00	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partion etc. as required complete.	6.00	Meter		
3.00	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
3.01	85 mm flexible cover	6.00	Meter		
3.02	Joints for 85mm width cover	4.00	Nos.		
3.03	base joints	6.00	Nos.		
4.00	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
4.01	3½ X 25 sq. mm (28mm)	4.00	No.		

SL No.	DESCRIPTION	Qty.	UNIT	RATE (In words & Figures)	AMOUNT
--------	-------------	------	------	------------------------------	--------

5.00 Supplying and installing following size of perforated painted with powder coating M.S. cable trays with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with M.S. suspenders including bolts & nuts, painting suspenders etc as required.

5.01 300 mm width X 50 mm depth X 1.6 mm thickness 62.00 Meter

Total Rs.



कर्मचारी अभियन्ता (पि)/B.E. (फिफ्ट)
 पञ्जाब प्रो. एंड. एडु. कॉन्फेड. काँग्रेस
 I.W.D. I.I. Kanpur

