

QUOTATION

Sub:- Repairing and replacement of electrical items wire, DLP, tube light, Switch/socket etc. in CESE-216, 217,209 & 220, C3i Lab, H.B, KD-219, BSBE lab-19 etc labs and offices at academic area on complaint basis.

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(In Words & Figures)					
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 1.5 sq. mm	8.00	Metre		
b	3 x 2.5 sq. mm	8.00	Metre		
2	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	12.00	Meter		
3	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
a	internal / external angle	1.00	Nos.		
b	changeable flat angle	6.00	Nos.		
c	flat junction	2.00	Nos.		
4	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	5.00	No.		
5	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.				

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In Words & Figures)	
a	20 watt ESENTIAL PHILIPS or equivalent Tube in place of 36/40 W FL tube	25.00	Nos.		
6	Alteration of internal wiring in existing fitting of any type for retrofitting of tube LED i/c dismantelling & refixing as read.	15.00	Nos.		
7	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	3.00	No.		
b	15/16 A switch	1.00	No.		
c	3 pin 5/6 A socket outlet	2.00	No.		
d	6 pin 15/16 A socket outlet	1.00	No.		
e	Blanking Plate	1.00	No.		
8	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	1 or 2 Module	1.00	No.		
b	3 Module	1.00	No.		
c	6 Module	1.00	No.		
9	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a	1 or 2 Module	1.00	Nos.		
b	3 Module	1.00	Nos.		
c	6 Module	1.00	Nos.		

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In Words & Figures)	
10	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	4.00	Nos.		
11	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	1.00	Nos.		
12	Supplying, installation, testing & commissioning of smoke detector with builtin LED and mounting base complete with all connections etc. as required.	4.00	No.		
13	Supplying, installation, testing & commissioning of manual call boxes of MS construction in surface/recess with stainless steel chain & hammer assembly complete with glass and push button etc. as required.	2.00	No.		
14	Supplying, installation, testing & commissioning of addressable manual call point complete as required.	7.00	No.		

Total Rs.

अडिप्टरी अडिपल (पि)/E.E. (Elect.)
सोडिपि, यरु पीरु हसुधर, कंगुर
I.W.D., I.I.T. Kangur

(Signature)