


QUOTATION

Name of work :- Making of temporary connection from feeder pillar No. 8 to flight laboratory AC unit feeder pillar to sustain the electrical supply for server on urgent basis at IIT Kanpur

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required.				
1.1	Above 185 sq. mm and upto 400 sq. mm	100.00	Mtr.		
2	Digging trench for taking out cable upto 400 Sq.mm. and refilling , watering ,ramming the same after taking out cable as reqd complete.	20.00	Mtr.		
3	Lifting removing cable of following size from trench/clamps, making roll & depositing the same in store I/c cartage.				
3.1	above 185 upto 400 Sq.mm.	100.00	Mtr.		
4	Supplying and making indoor end termination with brass compression gland, aluminum lugs for following size of PVC insulated & PVC sheathed/XLPE aluminum cable of 1.1kV grade as reqd.				
4.1	3½ X 400 sq. mm (82mm)	2.00	Nos.		

Total Rs.


अधिसायी अभियंता (वि०) E.E. (Elect.
संयोजक), माओपी संस्थान, कानपुर
I W.D., I.I.T., Kanpur

