


QUOTATION

Name of work:- Repairing/replacement of old & damaged LAN Wire House No 507 Upper Floor in Type - V.

S.No.	Description	Qty.	Unit	Rate	Amount
(in words & Figures)					
1	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.		
2	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	150.00	Mtr.		
3	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	20.00	Mtr.		
b)	25 x 16 mm	25.00	Mtr.		
4	Supply and laying of HDPE pipe ISI mark of 40 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.	80.00	Mtr.		
5	Laying of one no. PVC insulated, PVC sheathed / XLPE power cable of 1.1kV grade of size not exceeding 35 sq.mm.				
a)	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	85.00	Mtr.		
b)	On surface with MS clamp	5.00	Mtr.		

Total Rs.


अधिसारी अभियंता (वि) E.E. (Elect.
संक्रियवि, माध्यम संचालन, कानपुर
I.W.D., I.I.T., Kanpur
