

QUOTATION

Name of work : Providing additional power points for installation of AC units in VIP rooms of Auditorium.

S.No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a	3 x 4 Sq.mm..	15.00	Mtr.		
2	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a	15/16 Amp. switch	9.00	Nos.		
b	6 Pin 15/16 Amp. socket outlet.	9.00	Nos.		
c	Fan regulator socket type rotary step	1.00	Nos.		
d	Blanking plate	2.00	Nos.		
3	Supplying and fixing following modular base & cover plate on existing modular metal boxes etc. as reqd.				
a	3 module	2.00	Nos.		
b	8 module	1.00	Nos.		
4	Supplying and making indoor end termination with brass compression gland, aluminum lugs for following size of PVC insulated & PVC sheathed/XLPE aluminum cable of 1.1kV grade as reqd.				
a	2x10 sq.mm.	4.00	Nos.		
b	3½x 50 sq.mm.	2.00	Nos.		

S.No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
5	Supplying & Laying of one no. XLPE sheathed aluminum conductor steel armoured power cable of size 2 x 10 sq.mm. 1.1kV grade in following manners.				
a	On surface with MS clamp	80.00	Mtr.		
6	Supplying and fixing 40 amp to 63 amp rating 240 volts 'C' curve 10 kA MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd.				
a	Four Pole	5.00	Nos.		
7	Drawing of optical cable enhanced cat 5/cat 6/telephone/ networking /power cable in existing steel conduit pipe/GI /HDPE pipe including numbering of networking wire from room to rack as reqd.	600.00	Mtr.		
8	Dismantling & refixing brass compression type cable gland upto 35 sq.mm cable.	4.00	Nos.		
9	Dismantling the old conduit pipe/DLP/ wood batten of all sizes from surface/recessed & making good the damages l/c filling the holes of the surface etc as reqd.	30.00	Mtr.		
10	Dismantling and refixing of switch / socket /regulator l/c cleaning, connecting, commissioning etc as reqd.	40.00	Nos.		
11	Locating fault in the cable lines with fault locator and meggering of LT cable etc and rectifying removing & restoring the same and making good the damages etc as required.	1.00	Nos.		
12	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	2.00	Nos.		
13	Digging trench for taking out cable and refilling , watering ,ramming the same after taking out cable as reqd complete.	15.00	Mtr		
14	Supplying, fixing, connecting, commissioning & testing of Pedestal fan 400mm sweep AC 230/250V, 50Hz with all accessories complete. as reqd.	1.00	Nos.		

S.No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
15	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.				
a	Mini- trunking	5.00	Mtr.		
16	Providing and fixing DLP plastic trunking of size 105 mm x 50 mm without cover on surface as reqd.	30.00	Mtr.		
17	Providing and fixing DLP plastic trunking of size 105 mm x 50 mm accessories on surface as reqd.				
a	PVC trunking full cover of size 85 mm size	30.00	Mtr.		
b	End cap	6.00	Nos.		
c	Internal angle.	4.00	Nos.		
d	External angle	2.00	Nos.		
e	cover joint	13.00	Nos.		
f	Base joint	26.00	Nos.		
Total Rs					

अधिसाधी अभियता (वि०) E.E. (Elect.
संनिविदि, भाडसुी संस्थान, कानपु
I.W.D., I.I.T., Kanpur

(Signature)