

QUOTATION

Sub:- Replacement of damaged electrical items like wire, switch, socket MCB & LED lights etc in L-18, WL-102,129, 209A, JEE/GATE Office-211, 206, FB-382 etc other offices & labs in academic area on complaint basis.

SL No.	DESCRIPTION	QTY	UNIT	RATE <small>(In words & Figures)</small>	AMOUNT
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 2.5 sq. mm	21.00	Metre		
1.02	3 x 4 sq. mm	22.00	Metre		
2	Supply and fixing of 32 x 20 mm DLP mini-trunking white-system with independent cover etc. as required complete.	17.00	Meter		
3	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
3.01	Single pole 5 A to 32 A	1.00	No.		
3.02	Triple pole and neutral 5 A to 32 A	1.00	No.		
4	Alteration of internal wiring in existing fitting of any type for retrofitting of tube LED i/c dismantling & refixing as reqd.	18.00	Nos.		
5	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
5.01	3 Module	1.00	Nos.		
5.02	4 Module	1.00	Nos.		



SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
5.03	6 Module	3.00	Nos.		
6	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	1.00	Nos.		
7	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.				
7.01	20 watt ESENTIAL PHILIPS or equivalent Tube in place of 36/40 W FL tube	32.00	Nos.		
8	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
8.01	12 watt surface mounting LED light fixture	10.00	Nos.		
8.02	36 watt recess mounting LED light fixture 600 x 600 mm	8.00	Nos.		
8.03	36 watt recess mounting LED light fixture 300 x 1200 mm	1.00	Nos.		
9	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
9.01	5/6 A switch	6.00	No.		
9.02	15/16 A switch	5.00	No.		
9.03	6 pin 15/16 A socket outlet	5.00	No.		
10	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				

g

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
10.01	3 Module	1.00	No.		
10.02	6 Module	3.00	No.		
11	Supply, Installation testing and commissioning of following seep, copper wound, 900 RPM, 220 volt AC, 50 Hz exhaust fan in the existing opening etc as required complete.				
11.01	375 mm / 15" sweep	1.00	Nos.		
11.02	450 mm / 18" sweep	2.00	Nos.		
12	Supplying and fixing exhaust fan shutter for following sizes exhaust fan on rag bolts as reqd complete.				
12.01	for 375 mm / 15" sweep	1.00	Nos.		
12.02	for 450 mm / 18" sweep	2.00	Nos.		
13	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	19.00	Nos.		
14	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
14.01	6 A switch	3.00	No.		
14.02	20 A switch	1.00	No.		
14.03	6 A pin 2/3 pin socket outlet	3.00	No.		
14.04	6/16 A 3 pin socket outlet	1.00	No.		

8


SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
--------	-------------	-----	------	------------------------------	--------

15 Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.

15.01 3 module 2.00 Nos.

15.02 6 module 1.00 Nos.

Total Rs.


 अधीनस्थ अभियन्ता / S.E.
 संचालित (I.W.D.)
 गांधी संस्थान, कानपुर
 I.I.T., Kanpur
