

QUOTATION

Sub:- Providing and making power points on DLP in WL-204E.

S.N	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(In words & figures)					
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 4 sq. mm	70.00	Metre		
2	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	15.00	Meter		
3	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
3.01	End cap	2.00	Nos.		
3.02	internal / external angle	4.00	Nos.		
3.03	changeable flat angle	5.00	Nos.		
3.04	flat junction	1.00	Nos.		
4	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	15.00	Meter		
5	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
5.01	85 mm flexible cover	12.00	Meter		

S.N	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & figures)	
5.02	End cap	4.00	Nos.		
5.03	Internal angles- adjustable from 80°-100°	4.00	Nos.		
5.04	external angles- adjustable from 60°-120°	4.00	Nos.		
5.05	flat junction	1.00	Nos.		
5.06	flat angles	1.00	Nos.		
5.07	Joints for 85mm width cover	7.00	Nos.		
5.08	base joints	12.00	Nos.		
6	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
6.01	3 module	1.00	Nos.		
6.02	6 module	7.00	Nos.		
7	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
7.01	6 A switch	9.00	No.		
7.02	20 A switch	12.00	No.		

S.N	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
-----	-------------	-----	------	------	--------

(In words & figures)

7.03 6/16 A 3 pin socket outlet 12.00 No.

8 Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required. 3.00 No.

Total Rs.

९३
 अधीक्षक अभियन्ता / S.E.
 सोनिडिगि (I.W.D.)
 माओप्रौ सस्थान, बनारस
 I.I.T., Kanpur

[Handwritten signature]