

## QUOTATION

Sub:- Providing and making power & net points along with associated works at NL-I-212.

SL No.	DESCRIPTION	QTY	UNIT	RATE (Rs.) Words & Fig.	AMOUNT
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.1	3 x 2.5 sq. mm	125.00	Metre		
1.2	3 x 4 sq. mm	60.00	Metre		
1.3	3 x 16 sq.mm.	2.00	Meter		
2	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	35.00	Meter		
3	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
3.1	85 mm flexible cover	30.00	Meter		
3.2	End cap	6.00	Nos.		
3.3	Internal angles- adjustable from 80°-100°	5.00	Nos.		
3.4	external angles- adjustable from 60°-120°	4.00	Nos.		
3.5	flat junction	1.00	Nos.		
3.6	flat angles	4.00	Nos.		
3.7	separation partitions	20.00	Meter		
3.8	Joints for 85mm width cover	10.00	Nos.		
3.9	base joints	30.00	Nos.		
4	S & F following size of steel flexible pipe along with the accessories on surface etc as required				
4.1	32 mm	5.00	Meter		
5	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
5.1	3 module	10.00	Nos.		
5.2	6 module	26.00	Nos.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (Rs.) Words & Fig.	AMOUNT
6	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
6.1	6 A switch	58.00	No.		
6.2	20 A switch	4.00	No.		
6.3	6 A pin 2/3 pin socket outlet	58.00	No.		
6.4	6/16 A 3 pin socket outlet	4.00	No.		
7	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	200.00	Meter		
8	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. ( box and cover plate will be supplied by dept.)	10.00	Nos.		
9	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
9.1	16 way, Double door	1.00	No.		
10	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
10.1	Single pole 5 A to 32 A	16.00	No.		
10.2	Double Pole (40A-63A)	1.00	Nos.		

9

SL No.	DESCRIPTION	QTY	UNIT	RATE (Rs.) Words & Fig.	AMOUNT
11	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket outlet and complete with connections, testing and commissioning etc. as required.	2.00	No.		
12	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
12.1	6 /10/16 Sq.mm.	6.00	Nos.		
13	Dismantling concealed & damaged DB/TPN Switches/starter/ loose wire boxes along with all accessories and depositing the same in the sectional store repairing the damages as reqd complete.	15.00	Nos.		
14	Dismantling the old conduit pipe/wood batten of all sizes from surface/recessed & making good the damages I/c filling the holes of the surface etc as reqd. and depositing it in sectional store.	75.00	Meter		

**Total Rs.**

अधीक्षक अभियन्ता / S.E.  
संविधिक (I.W.D.)  
गांधी सांस्थान, कानपुर  
I.T., Kanpur

*[Handwritten Signature]*

*[Handwritten Signature]*