


QUOTATION

Name of work:-Locating faults ,digging,making joints and replacement of faulty part of power cable damaged due to digging works near Asharam Bagiya and behind Hall-IX in the campus.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 kV grade as required.				
a)	3-1/2 x 70 sq.mm.	2.00	Nos.		
2	Excavation for foundation in soft soil including dressing of sides and ramming of bottoms, lift upto 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 metres.	25.00	Cum		
3	S & Laying of one no. XLPE cable aluminum conductor steel armoured power cable of 1.1kV grade of size 3-1/2x70 sq.mm. in following manners.				
a)	In Ground including excavation, sand cushioning brick protecting covering and refilling the trench etc. as reqd.	115.00	Mtr		
4	Lifting & removing cable of following sizes from trenches or clamped on surface, making roll depositing the same in the store l/c cartage etc as reqd.				
a	up to 70 sq.mm.	10.00	Mtr.		
5	Locating fault in the cable lines with meager etc. and rectifying removing & restoring supply the same & making good the damages etc as reqd.	1.00	Nos.		

Total Rs.


ಇಂಜಿನಿಯರಿಂಗ್ ವಿಭಾಗ
ಪ್ರಾಚಾರ್ಯರ ಕಛೇರಿ
I.I.T. Kanpur
