


INDIAN INSTITUTE OF TECHNOLOGY, KANPUR
INSTITUTE WORKS DEPARTMENT
DIVISION-I

SI.	Description of items	Unit	Qty	Rate	Amount
	Minor civil maintenance work				
1.	<p>Providing & fixing temporary barricading, made with 0.5 mm thick colour coated sheet of size 1.025 m x 3.048 in screwed to vertical & horizontal MS tube of size 50x50x3 mm, fixed with wall columns by means of necessary MS L- brackets welded to tubes & expandable dash fasteners of size 10 mm x120 mm size etc. complete.</p> <p>The barricading provided shall be retained in position at site continuously during the execution of the entire work till its completion or up to 1.5 years. Rate includes its maintenance for damages, all incidentals, labour materials, equipments and works required to execute the jobs. The barricading shall not be removed without prior to approval of Engineer-in-charge. If the barricading is required to be reshifted as per site requirement, the labour charge shall be payable. (Note: The barricading provided shall remain to be the property of the contractor on completion of the work or period.)</p>	Sqm	138.75		
	Total				
	GST @ _____				
	G. Total				


Executive Engineer