

INDIAN INSTITUTE OF TECHNOLOGY, KANPUR
INSTITUTE WORKS DEPARTMENT
DIVISION-I

SI.	Description of items	Unit	Qty	Rate	Amount
	Minor civil maintenance work				
1.	<p>Providing & fixing temporary barricading height upto 2.60 m from ground level all round the construction area, made with 0.5 mm thick colour coated sheet of size 1.025 m x 3.048 m screwed to vertical MS tube of size 50x50x3 mm, placed 3.00 m c/c including necessary excavation in digging holes of size 45x45 cm & upto 60 cm depth and filling with plain cement concrete 1:5:10 (with 40 mm brick bats) upto 500 mm depth after placing post and covered with 100 mm plain cement concrete 1:2:4 etc complete.</p> <p>The barricading provided shall be retained in position at site continuously during the execution of the entire work till its completion or up to 1.5 years. Rate includes its maintenance for damages, all incidentals, labour materials, equipments and works required to execute the jobs. The barricading shall not be removed without prior to approval of Engineer-in-charge. If the barricading is required to be reshifted as per site requirement, the labour charge shall be payable. (Note: The barricading provided shall remain to be the property of the contractor on completion of the work or period.)</p>	Rm	84.10		
	Total				
	GST @ _____				
	G. Total				

Subs 3/11/23
Executive Engineer