

INDIAN INSTITUTE OF TECHNOLOGY KANPUR
Dean of Infrastructure & Planning

NIT No.- QT/09-05-2024-05

N/W- Providing and fixing internal & external signage at ESB 3

Fill up here

Item no.	Description	Unit	Qty	Estimated Rate without GST (Rs)	Estimated Amount without GST (Rs)	Quoted Rate without GST (Rs)	Quoted Amount without GST (Rs)
1	P/F Signages of size 18x9 Inch with 3 mm Aluminum Composite Panel (ACP) Sheet and fluorescent base pasted on Acp sheet with 3 M vinyl sheet having minimum thickness of 90 micron cut & pasted i/c fixing of signages with SS studs of suitable size i/c drilling holes and fixing etc. complete as per approved sample & direction of Engineer- In- Charge.	Each	28	750.00	21000.00		
2	Supplying & Installation of Signage, fabricated of 3 mm Aluminum Composite Panel (ACP) exterior grade sheet with a retro reflective type IV grade media of 3M brand in double layer sticking on the ACP Sheet as per approved design i/c necessary SS screws etc. all complete as per direction of Engineer- In- Charge.	Sqft	24	600.00	14400.00		

3	Providing and fixing in position, 304 Grade Stainless Steel frame fabricated of Stainless-Steel square & round tubes of specified size and design fixed to vertical Stainless Steel round tubes of specified diameter and length for installation of signage board complete as per approved design & direction of Engineer- In- Charge. The rate is excluding of excavation and concrete work.	Kg	25	650.00	16250.00		
		Estimated Amount (A) =		Rs. 51,650/-		Quoted Amount (B) =	Rs.
		Percentage (%) = $\frac{B-A}{A} \times 100$					

SRK

Dean of Infrastructure & Planning