## Name of work: Furnishing of residential and other utility of guest room buildings at Extension Center NOIDA (31 Single Seated Rooms)

.No.	Descriptions	Qty.	Unit	Rate	Amount	Remarks
	Description					
1	Providing and Fixing in position the main entrance flush door of overall size 2100x900 on existing aluminium door frame fixed at site. The door shall consist of 35mm thick BWP flush door having 1mm thick laminate on both side in single piece, with 8mm thick teak wood leaping all around duly melamine polished in matching shade of approve laminate on 4nos of heavy duty SS hinges of 100mm x 75mm x 3mm thick Dorset Make. The cost of door is inclusive of butt hinges,door closer,security chain,door stopper Dorset Make and fixing of owner supplied free of cost Electronic Mortise lock.	31	No		-	
2	Providing and Fixing in position the toilet entrance flush door of overall size 2100x700 on existing aluminium door frame fixed at site. The door shall consist of 35mm thick BWP flush door having 1mm thick laminate on both side in single piece, with 8mm thick teak wood leaping all around duly melamine polished in matching shade of approve laminate on 4nos of heavy duty SS hinges of 100mm x 75mm x 3mm thick Dorset Make. The cost of door is inclusive of butt hinges,door stopper,Mortice Lock with one side knob Dorset Make	31	No		-	
3	Providing and Fixing in position the Balcony flush door of overall size 2100x900 on existing aluminium door frame fixed at site. The door shall consist of 35mm thick BWP flush door having 1mm thick laminate on both side in single piece, with 8mm thick teak wood leaping all around duly melamine polished in matching shade of approve laminate on 4nos of heavy duty SS hinges of 100mm x 75mm x 3mm thick Dorset Make. The cost of door is inclusive of butt hinges,door stopper,Mortice Lock with one side knob, Door Closer Dorset Make	32	No		-	
	Total of Doors (A)					
	round boots (n)					
В	Furniture					-
1	Providing and fixing in position Bed of overall size 1950mm (L) x1050mm (W) x 325mm (H). The structure shall be made of 25mm thick peripherial BWP block board with 19mm bwp board on the top to receive the mattress with required M.S support for stability. The Peripherial frame of 25mm thick board will have 1mm thick laminated on outer side with 8mm thick teak wood leaping duly melamine polished with matching shade of laminate. All inner surfaces will be applied anti termite oil and duly painted with enemal paint surfaces including top shall be lined with laminate. of appd stain	62	No		-	
2	Providing and fixing in position Head Board of overall elevation size 1050mm (L) x 900mm (H) Base shall be made out of 25mm thick block bord and bwp ply. The job shall be completed with 1mm thick Laminate as per approve shade and leatherite cladded foam with invisible/overlaping stiching and latherite cladded buttons.	62	No		-	



S.No	Descriptions	Qty.	Unit	Rate	Amount	Remarks
3	Providing and fixing in position Bed side drawer unit of overall size 550mm x 450mm x 400mm as per ref.image. The Basic structure shall be made out of 25mm thick BWP block board with 8mm thick lipping duly melamined with matching shade of laminate and bwp ply. All exposed and internal surfaces including top shall be lined with 1mm thick Laminate as per approved shade. The Drawer internal side to have 1.0mm matching laminate. The job shall include s.s hardware, telescopic channel etc.	62	No		-	
4	Providing and fixing in position wardrobe of overall size 1050mm (W) x 2250mm (H) x 600mm (D) as per ref. image Basic structure shall be made out of 25mm thick block board with 8mm thick teak wood lipping and BWP ply.The Shutter of wardrobe shall be made out of 19mm thick BWP board. 1.0mm thick Laminate shall be lined on all expossed and internal surfaces. Inside to have shelving unit with 1mm laminate as per approve shade,laminated shelves,partitions shall be provided as per the mockup for safe,Shoe Rack, Light Pelmet etc.The cost shall be inclusive of p/fixing s.s hanger rod, telescopic channel and other hardware.	83.70	Sqm		-	
5	Providing and placing in position Luggage rack of overall size 1050mm (L) x 600mm (D) x 800mm (H) with drawers and platform as per ref. image. The Basic box shall be made out of 25mm thick block board with 8mm thick teak wood lipping duly melamine polished matching with approved laminate. All the exposed and internal surfaces shall be lined with 1mm thick Laminate of approve shade. The job shall inclusive of p/fixing of 6no. of 12mm x 12mm s.s Bars 1000mm long fixed on laminated top and hardware.		No			
6	Providing and placing in position study table of overall size 1050mm x 600mm x 750mm with drawers as per ref. image box shall be made of 25mm thick block board with 8mm thick teak wood lipping duly melamine polished with matchingand bwp ply. All the exposed surfaces shall be lined with laminate. Inner side of drawer to have 0.8mm laminate (223 hiland pine EURO) lining. The job shall include all s.s Hardware and telscopic channel etc.		No		-	
7	Providing and placing in position Fridge cum Unit with inbuilt fridge of overall size 1500mm x 600mm x 800mm with drawer As per ref. image. The Base box shall be made out of 25mm thick block board with 8mm thick teak wood lipping duly melamine polished matching with approved shade of laminate. All the exposed and internal surfaces shall be lined with 1mm thick laminate of approved shade. The job shall include all s.s hardware and making of Vent Holes for Fridge exhaust.	31	No		-	
8	Providing and placing in position Coffee table chair as per the ref. image. The chair shall be made of oak wood duly melamined polished in the approved shade and shall have the arm rest and curved back, all foam and rubber shall be used on the best quality and cost of the fabric shall be Rs. 600/- RM	31	No		-	



S.No.	Descriptions	Qty.	Unit	Rate	Amount	Remarks
9	Providing and placing in Study table chair as per the ref. image. The chair shall be made of oak wood duly melamined polished in the approved shade and shall be without arm rest but with curved back, all foam and rubber shall be used on the best quality and cost of the fabric shall be Rs. 600/- RM	31	No		-	
	Providing and placing in position the wooden Coffee table as per the ref. image, with above specification and with 12mm toughned glass top. Size of the table shall be 600x 1200		No		-	
	P/fixing long mirror comprising of 35x25 oak wood frame, 5mm saint Gobain mirror with 6 mm commercial ply. The oak wood frame shall be melamine polished in the matching shade and back ply shall be enamel painted with necessary hanging arrangement as per approval. Size: 450 x 1500 mm		No			
	Total of Furniture Items				-	
С	FINISHING AND FURNISHING WORKS					
	Providing and doing three or more coat on the wall velvet touch paint (ICI DULUX) on p.o.p/ ply surface as per appd. colour and shade ( for colour refer FFE). The job shall include doing primer coat and acrylic putty filling on the exisiting POP surfaces etc. complete. The job shall be done as per manufacturer's specification.		Sqm.		-	
	Providing and doing three or more coat on ceiling velvet touch paint (ICI DULUX) on p.o.p/ ply surface as per appd. colour and shade ( for colour refer FFE). The job shall include doing primer coat and acrylic putty on exisitng POP surface etc. complete. The job shall be done as per manufacturer's specification.		Sqm		-	
	Providing and making Pelmet drop of approximate size 900x150 as per the ref. image made of 19mm BWP block board with lipping etc.	155	Sqm		-	
	Total of Finishing and Furnishing Item ('C)				-	

